



City of Morden  
Operations  
100-195 Stephen Street  
Morden, MB R6M 1V3  
[tel] 204-822-4434  
[fax] 204-822-6494

## Addendum 1

### Contract 3-2019. Storm Sewer Works

---

The City of Morden provides the following clarifications to the contract:

To Section C: S Railway storm sewer installation:

1. All catch basins are roughly 1.1m from the top of the grate to the pipe invert, no sumps;
2. The ditch to be backfilled with common material. Total fill quantity is approximately 16,400 cubic yards.
3. The fill is supplied by the City, and to be hauled by a contractor within the city's limits.
4. Include the cost of the hauling and placing said common material in your unit price for the pipe installation.

Sincerely,

Tatiana Sinchenko  
*City of Morden*  
*Engineering Assistant*